

Approved For Release 2001/08/02 : CIA-RDP78-02820A000700060063-9

22 August 1961

## MEMORANDUM FOR THE RECORD

FROM: [REDACTED]

25X1A9a

SUBJECT: Estimated Construction Costs, [REDACTED] Transmitter Site

25X1A6a

On 18 August 1961 at a meeting of OC-MD, OC-E, and OL/RECD representatives, the following estimates of construction costs of the [REDACTED] Transmitter Site were made:

25X1A6a

1. Building, 56' x 25' at \$15. sq. ft.	\$21,000.
2. Water, Electric Power & Phone Connections	2,500.
3. Septic Tank & Seepage Field	750.
4. Fuel Tank, 1,000 Gal.	300.
5. Installation & Wiring of 75 KW Generator	400.
6. Fence	1,200.
7. Access Road & Gravel Parking	5,660.
8. Storm Drains	1,700.
9. Antenna Bases & Anchors (8 towers)	600.
10. Trenching & Backfill (coax)	200.
11. Antenna Erection Labor	400.
12. Antenna Site Survey	200.

Total	\$34,910.
Round off	35,000.
15% Contingency	5,250.
TOTAL EST. COST	\$40,250.

25X1A9a

## Distribution:

Original - Routing/File  
 2 - Monthly Report  
 2 - OC-MD  
 1 - OL/RECD  
 1 - SEB Chrono

~~SECRET~~